


Key to Materials

1	Alucobond light grey 104 cladding (to be removed & replaced with aluminium cladding color RAL 9006 Matt)
5	Yellow brick - leicester multi cream
6	Blue engineering brick
7	Clear double glazed windows/doors
7a	Opaque double glazed screens
9	Clear toughened balustrade glass
10	Aluminium window frames powder coated - RAL 7037
11	Aluminium louvers powder coated - RAL 7047
12	Timber handrail
13	Aluminium infill panels powder coated - RAL 7004
14	Aluminium capping - RAL 7037 (brick)
15	Alucobond light grey 104 coping
16	Steel edge trim - RAL 7037
20	Aluminium cill flashing - RAL 7037 (to be removed temporarily & reinstated)
21	Aluminium lattice frame channel - RAL 7037

Notes

1. All dimensions are in millimeters.
2. Dimensions are not to be scaled directly from this drawing.
3. All dimensions are to be checked on site and the Architect is to be informed of any discrepancies before construction commences.
4. All references to drawings refer to the current revision of that drawing.
5. Structural and services information shown is indicative only. Refer to Consultants drawings for details and setting out.



KEYPLAN

NORTH ELEVATION
dwg 1486-C-H140

WEST ELEVATION
dwg 1486-C-H143

EAST ELEVATION
dwg 1486-C-H141

SOUTH ELEVATION
dwg 1486-C-H142

CDM

Significant Risks and Hazards :

No Significant Risk

Key Design Decisions to Reduce or Eliminate Hazards :

KEY:

- Alucobond ACM panels to be removed
- Panels, copings and pressing to be removed temporarily and reinstated

Rev	Description	Date	By	Chk

buj architects

35 Millharbour
London
E14 9TX

Tel: 020 7531 3300
Fax: 020 7531 3301
e-mail: buj@buj.co.uk

Job title
New Capital Quay

Drawing title
East Planning Elevation

Drawn by	Date	Scale @ A0
aa	Jan 2019	1:50

Checked	Date	Issued for
--	--	PLANNING

Job No.	CI/SfB Ref.	Project Status	Drawing No.	Revision
1486	--	P	H141 -	